



Rev.	Date	Description
T1	03.08.2022	ISSUED FOR TENDER

- Insulation Notes**
- Existing metal clad walls has R2.0 insulation
 - All floors to have minimum R4.0 insulation
 - Existing roof to have R8.0 ceiling insulation
 - Proposed roof to have R8.0 ceiling insulation and vapour permeable sarking Enviroseal HTF-IT or similar below metal roof sheet.

New Walls

CEILING SERVICES LEGEND

	PENDANT LIGHT FITTING. SET 1800mm FROM FFL TO UNDERSIDE OF FITTING.
	RECESSED DOWNLIGHT FITTING.
	RECESSED DOWNLIGHT FITTING.
	SURFACE MOUNTED DOWNLIGHT FITTING.
	WALL MOUNTED LIGHT FITTING. SET @ 2100mm ABOVE RELEVANT FFL.
	CEILING MOUNTED BATTEN LIGHT.
	CEILING RECESSED EMERGENCY LIGHT.
	SURFACE MOUNTED SMOKE DETECTOR.
	EMERGENCY ALARM BELL.
	MOTION SENSOR.
	SURFACE MOUNTED EXIT SIGN.
	CEILING RECESSED EXTRACTION FAN.
	THERMAL DETECTOR.

NOTE: Ceiling finishes and fixtures/lighting only. Refer to electrical engineers drawings and specifications for more details and power requirements. Contractor to refer to architects drawings for setbacks and heights.

maddison architects

maddison architects Pty Ltd | 1st Floor 98 Bank St. South Melbourne VIC 3205 | 03 9646 3636
maddison@maddisonarchitects.com.au | Abn: 91 007 215 643 | reg no: C50263

project: Falls Creek Primary School Redesign
project address: 15 Slalom St, Falls Creek VIC 3699

client: Victorian Schools Building Authority (VSBA)

drawing: RCP - GROUND FLOOR

drawing number	revision	drawn	checked
A300	T1	AF	PM

scale: 1 : 50 @A1

date: 03.08.2022

stage: TENDER - NFC

north

Notes

- All existing conditions, dimensions and levels to be checked on site prior to commencing construction.
- All existing levels are indicative only. Survey drawing to take precedence over architectural drawings.
- Builder to refer any inconsistencies to the Architect for clarification.
- Builder to check that this drawing is the most recent amendment.
- Do not scale the drawings.